BRUHAT BANGALORE MAHANAGARA PALIKE, YALAHANKA ZONE

Executive Engineer
Byatarayanapura Division
B.B.M.P., Bangalore - 92
T.N.GL Dated:

Draft SCHEDULE-B

Issued to :

Original / Duplicate
Item No.

Name of Work : Detailed Estimate for The work of Construction of CC Drain at kodigwhalli village in ward no 8, Kodigehalli sub division

Sl. No	Approved Quantity	Description	Unit	Sanctioned Rates	Rates Quoted by the	
				In Figures	Figures	In Words
1	89.24	KSRRB 300-1. Earthwork excavation by manual means in Hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications. MORTH Chapter 3 (Page no 150, Item no. 19.2 of BCSR 2012-13)	Cum	81.00		
2	271.35	Removing B.S. slab of Drain and stacking. (Page no 28, Item no. 5.32 of BCSR 2012-13)	Sqm	44.47		
3	29.84	KSRB 4-1.3: Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @ 180kgs, with 40mm and down sze graded granite metal coarse aggregates @ 0.85 cum and fine aggregtes @ 0.57 cum machine mixed machine mixed concrete laid in layers not exceeding 15cms thick well compacted in foundation and plinth including cost of all materials labour HOM of machinery curing complete as per specifications . (Page no 12, Item no. 5.32 of BCSR 2012-13)	Cum	3884.76		
4	77.54	KSRB 4.2.2 : Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal, coarse aggregates @ 0.878cum and fine aggregtes @ 0.459cum with superplastisiser @ 3 lts confirming to IS 9103-1999 Reaffirmed-2008 machine mixed concrete laid in layers not exceeding 15cms thick vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintles, retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications.. (Page no 13, Item no. 4.11 of BCSR 2012-13)		5239.08		
5	678.15	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per pecificaitons.(P-17 Item No. 4.31 2012-13 SR)	Sqm	244.08		
6	38.77	KSRB 4.9.2 : Providing T.M.T. Steel reinforcement for R.C.C. work including straightening, cutting, bending, hooking , placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3. (Page No. 19& Item No. 4.46)	Qtl	7323.48		

7	89.24	KSRRB M100-1 Loading and Unloading of Stone Boulder / Stone aggregates /Sand/ Kanker / Moorum.KSRRB M100-1 : Placing tipper at loading point, loading with front end loader,dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications.MORTH Chapter 1 (Page no 197, Item no. 24.41 of BCSR 2012-13)	Cum	72.30		

Signature of the Contractor
Reg. No.
Postal Address

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

ಕರಡು ಟೆಂಡರ್ ಷಡ್ಯೂಲ್‌ನ್ನು
ತಿದ್ದುಪಡಿಗಳ ಸಂಖ್ಯೆ .....
ತಿದ್ದುಪಡಿ ಮಾಡಿ/ಇಲ್ಲದೆ
ಅನುಮೋದನೆ ನೀಡಲಾಗಿದೆ.

ಅಧೀಕ್ಷಕ ಅಭಿಯಂತರರು
ಯಲಹಂಕ ವಲಯ
ಬಿಬಿಎಂಪಿ, ಬೆಂಗಳೂರು-92

18/01/2013